

# VHX-67C-PU


Dakota Digital VHX Instrument Installation  
For '67-'72 Chevy Pickup Systems

Your new VHX-67C-PU kit should include:



## Installation

1. Remove the stock gauges from the dash. Remove the eight screws holding the gauges to the bezel on the back of the system. These screws will be used to secure your VHX system in the stock bezel.



2. Remove the stock gauges, separator plate, and lens from the bezel. The only item to be reused is the original front bezel; the other pieces can be discarded. Now is a good time to clean the bezel and remove any dirt or old lens gasket material.




- 3a. Remove the protective tape from the clear lens and install the VHX system into the bezel. Watch carefully as you insert the system so you don't scratch or damage the lens.

- 3b. The VHX system should align tightly and the lens should sit flush with the bezel.






4. Secure the VHX system to the bezel with the eight screws removed from the stock gauges.



5. Connect the CAT5 cables and the 3 pin harness to the system so they can be routed and connected to the control box as the system is re-installed.



6. Re-install the cluster into the truck and refer to the main manual for wiring instructions to complete the VHX installation.



4510 W. 61<sup>st</sup> St. N., Sioux Falls SD 57107  
Phone: (605) 332-6513 Fax: (605) 339-4106  
[www.dakotadigital.com](http://www.dakotadigital.com)  
[dakotasupport@dakotadigital.com](mailto:dakotasupport@dakotadigital.com)