


HDX-53C-VET / RTX-53C-VET

Dakota Digital HDX/RTX Instrument Installation For 1953 - '57 Corvette

Your new 53C-VET kit includes:






Installation


1. Remove the original instruments from the dash. This can be done by removing the two nuts attaching each gauge to the factory mounting studs behind the dash. Retain these nuts for installation of the new HDX or RTX system.




2. Secure the new HDX/RTX Instruments to the dash re-using the original nuts (1) from step one. In case of excess tightness, some trimming or grinding on the bottom of the reinforcing bracket (2) may be necessary to fit the instruments in the dash.



3. Connect the central dash gauges together using the provided Interconnect Harness. From the back side of the clusters the Volts/Oil will be on the left side and Fuel/Temp will be on the right side.



4. Connect the male end of the provided Y-Harness to the Interconnect Harness. The two provided 36" Main Harnesses will then be connected to the open ends of the Y-Harness. Carefully route one Main Harness up to the speedometer, and the other to the HDX / RTX Control Box mounting location.



5. Connect the Main Harness routed to the speedometer in step four. The provided Buzzer may also be connected (optional, for audio feedback).



6. Connect the provided Clock Harness to the back of the system's clock. Carefully route the other end to the Control Box mounting location.



7. Refer to the Main Manual for wiring instructions to complete the HDX or RTX installation.





▲ WARNING: This product can expose you to chemicals including lead, which is known to the State of California to cause cancer and birth defects or other reproductive harm. For more information go to www.P65Warnings.ca.gov



4510 W. 61st St. North Sioux Falls, SD 57107 www.dakotadigital.com dakotasupport@dakotadigital.com Phone (605) 332-6513 Fax (605) 339-4106

© Copyright 2022 - Dakota Digital